

11-19
15-065-01923-0000 209
R

4-031611

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -
SE NW NW /4 SEC. 24, 10 S, 25 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5783 Lease Knoll well # 4

Operator: Galloway Drilling Co. Inc. County Graham 136.01

Address: 105 So. Broadway
Wichita, Ks. 67202
Well total depth 4185 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 174 feet

Aband. oil well __, Gas well __, Input well X, SWD __, D & A __

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 19 Month: November Year: 91

Plugging proposal received from: Dale Loomis

Company: Galloway Drilling Co. Inc. Phone: _____

Were: 8 5/8" set @ 174' w/125 sx. 5 1/2" @ 4175' w/200 sx. Perf.
2068' w/500 sx. cwc. P.B.T.D. 4137'. Perf. 3733' - 3933'. Order
400 sx. 65/35 pozmix - 10% gel. - 500# hulls. Allied Cement Company.
L & M Water Trucks. Hole open to perf. and taking fluid. Pulled
tubing and packer in good condition.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:00 P.M., Day: 19, Month: November, Year: 91

Actual plugging report: Backside full of cement to surface tested to
300#. Squeezed 5 1/2" w/400 sx. cement blend w/500# hulls mixed into
last 200 sx. to max. P.S.I. 500#. Close in P.S.I. 300#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

DEC 02 1991

Remarks: _____
Conservation Division
Wichita, Kansas

INVOICED I did [] / did not [] observe the plugging.

Carl Goodrow

DATE 12-6-91
WV. NO. 34035

J. S.

(agent)
Form CP-213