

11-1915-065-01924-0000

031612

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

NW NW NW 1/4 SEC. 24, 10 S, 25 W
4950 feet from S section line
4950 feet from E section line

Operator license# 5783 Lease Knoll well # 5

Operator: Galloway Drilling Co. Inc. County Graham 128.73

Address: P.O. Box 158 Well total depth 3961 feet
Garfield, Kansas 67529 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 192 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 19 Month: November Year: 91

Plugging proposal received from: Dale Loomis

Company: Galloway Drilling Co. Inc. Phone:

Were: 8 5/8" set @ 192' w/150 sx. 5 1/2" @ 3959' w/150 sx. P.B.T.D.
3932'. Perf. 3856' - 3917'. Squeezed from 2000' w/450 sx. to surface.
Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls. Allied Cement
Company. L & M Water Trucks. Pulled rods - tubing. Hole open to
perfs and taking fluid.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:15 P.M. Day: 19 Month: November Year: 91

Actual plugging report: Squeezed 5 1/2" w/325 sx. cement blend
w/400# hulls. Mixed in to max. P.S.I. 1200#. Close in P.S.I. 1000#.
Squeezed 8 5/8" w/100 sx. cement blend w/100# hulls mixed into max.
P.S.I. 400#. Close in P.S.I. 200#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1991

Remarks: Anhy. 2077'.

INVOICED

I did not observe the plugging.

Carl Goodrow

DEC 12 1991

DATE

INV. NO. 34186

G.S.

(agent)

Form CP-2/3