

6 030369

API NUMBER 15-065-22,114-0000 *P*

SW, SEC. 24, T. 10 S, R. 25 WE

1650 feet from N/S^E section line

4290 feet from N/E^{SE} section line

Lease Name KNOLL Well # 1

County GRAHAM 131.95

Well Total Depth 4060 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 262 ✓

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5273

Operator: KIDWA EXPLORATION Co.

Name & Address 110 S. MAIN SEE. 510

WICHITA KANSAS

67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRUG License Number 182

Address 801 UNION CENTER WICHITA KANSAS 67202

Company to plug at: Hour: A.M Day: 16 Month: 12 Year: 19 84

Plugging proposal received from BILL CRAIG

(company name) ABERCROMBIE DRUG (phone) _____

were: ORDER 190 SX. 50/60 2 1/2 GEL 3 1/4 + 2 SX. CEMENT FLAKE - 1 - 8 5/8 WIPER PLUG.

SPOT WITH D.P. WITH HEAVY MUD IN HOLE AND NO FLUID LOSS

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30AM Day: 16 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT RAN D.P. TO 2170 BROKE CIRC. DISPLACED WITH 25 SX. CEMENT

PULLED D.P. TO 1250' DISPLACED WITH 100 SX. CEMENT PULLED D.P. TO 260' DISPLACED

WITH 40 SX. CEMENT PULLED D.P. SET WIPER PLUG @ 40' WITH HULLS AND 10 SX.

CEMENT TO BOTTOM CELLAR. CIRCULATED 15 SX. IN RATHOLE.

ELEV. 2509 ANNY 2164-99 RESTARTS NO LOG OR. 4000
STATE CORPORATION COMMISSION

Remarks: _____
(If additional description is necessary, use BACK of this form.)

JAN 02 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)

Dec 28 84

1-16-85
6526