

15-065-20143-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D. G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name Custer Well No. 1

Location SE-NE-NW Sec. 18 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4075

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C & G Drilling Company,

Address: 1107 Union National Bldg., Wichita, Ks. License No.

Operation Completed: Hour 4:30 AM Day 22 Month 5 Year 1968

The Above well was plugged as follows:

158'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru DP
from 1275' to 950'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from 180' to
120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 5/27/68
INV. NO. 7815-W