

15-065-20170-0000



KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dane G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name Hanna Well No. A-4

Location NE-NW-NE Sec. 18 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4065

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: C & G Drilling Company,

Address: 1107 Union National Building, Wichita, Ks. License No.

Operation Completed: Hour 1:00AM Day 13 Month 9 Year 1968

The Above well was plugged as follows:

164'--8 5/8" Surface casing, cement circulated with 130 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/16/68
INV. NO. 8470-W

Signed: W. L. Nichols
Well Plugging Supervisor