

15-065-20596-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company,

Complete Address 1130 KSB & T Building, Wichita, Kansas.

Lease Name Waldt Well No. 1

Location NW-NW-SW Sec. 18 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4025'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 5:30 PM Day 27 Month 3 Year 1973

The above well was plugged as follows:

262'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1015'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 110 Cu. Ft. cement
thru DP from 1240' to 915'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 4/3/73
INV. NO. 9205-W