

15-065-00786-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Schreiner Well No. C-1

Location NE-NE-NW Sec. 23 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4190'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:30 PM Day 15 Month 1 Year 1970

The above well was plugged as follows:

111'--8 5/8" Surface casing, cement circulated with 75 Sx.
3998'--5 1/2" Production casing, cemented on bottom with 100 Sx. Well plugged back to
3970'. Top perforations @ 3750'.

Sanded well back to 3650' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with
90 Sx. cement from 1175' to 885' then 19 sacks gel from 885' to 125' and finally 45
Sx. cement from 125' to bottom of cellar. Maximum pump-in pressure--300#. Final
shut-in pressure--150#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: M. L. Nichols
Well Plugging Supervisor

JAN 19 1970

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1/19/70
INV. NO. 1277-4