

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dorchester Exploration, Incorporated,

Complete Address 1204 Vaughn Building, Midland, Texas.

Lease Name Beard Well No. 1

Location APP C. 5E14
1450' FSL & 1450' FEL of Sec. 36 Twp. 20 Rge. (E) (W) 41

County Greeley Total Depth 2780'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sterling Drilling Company,

Address Box #129, Sterling, Kansas. License No.

Operation Completed: Hour 8:00 AM Day 26 Month 2 Year 1973

The above well was plugged as follows:

345'--10 3/4" Surface casing, cement circulated with 300 Sx. (9" Hole).
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 140 Cu. Ft. cement
thru DP from 1175' to 860'. Pulled DP to 340' and displaced 40 Cu. Ft. cement thru
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 20 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Nichols
Well Plugging Supervisor

DATE 2/28/73
INV. NO. 4060-W