

15-065-20177-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-28-1968
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tomlinson Oil Company, Incorporated,

Complete Address: 1125 Wichita Plaza Building, Wichita, Kansas.

Lease Name Knoll Well No. 1

Location NW-NE-SE Sec. 22 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 12:30PM Day 24 Month 10 Year 1968

The Above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru
DP from 875' to 550'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from 275'
to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/28/68
INV. NO. 8907-11