

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Derrick-American Oil, Incorporated,

Complete Address 355 R. M. Garvey Building, Wichita, Kansas.

Lease Name Brungardt Well No. A-5

Location SW-NW-SW Sec. 22 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 335'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Lost circulation @ 255', well abandoned.

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 8:15 AM Day 5 Month 2 Year 1971

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated.

Ran float on measuring line and found fluid level static @ 75'. Mixed 30 Sx. cement with 5% calcium chloride and ran open ended and followed with 3 Bbl. water and let set 2 hours. Ran measuring line, found fluid level had fallen to 110' and found top of cement @ 200'. Filled hole with heavy gel mud to 30' and 10 Sx. cement to bottom of cellar. (Mudding and cementing by Globe Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/8/71
INV. NO. 3318-W