

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name American Drilling Company, Limited,  
Complete Address 360 Sutton Place, Wichita, Kansas.  
Lease Name Knoll Well No. 3  
Location CE/2-W/2-SE Sec. 22 Twp. 10 Rge. (E) (W) 25  
County Graham Total Depth 4020'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 11:00 AM Day 22 Month 4 Year 1971

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated with 205 Sx.  
Top of Dakota section @ 1025'. ((LANDOWNER REQUESTED SURFACE CASING BE LEFT OPEN TO  
BE USED AS A FRESH WATER WELL)).

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP to 185' and circulated clear water.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/29/71  
INV. NO. 3614-W