

\$0.00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19708-00-00  
Spot: NWSEENW Sec/Twnshp/Rge: 11-35S-11E  
4334 feet from S Section Line, 3195 feet from E Section Line  
Lease Name: SPRINGS Well #: 8  
County: CHAUTAUQUA Total Vertical Depth: 1100 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

PLUGGING FEES  
WAIVED PER DL  
3/16/10.

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/18/2009 2:30 PM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: 50' plug at 1100', 50' plug at 650' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/19/2009 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:  
Ran 1" to 1100' gelled hole and spotted 5 sacks of cement. Pulled 1" and perforated at 650' and 350'. Next day ran 1" to 650' and spotted 5 sack plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 222 sacks of cement were used to plug well. Well was cut off and location restored.

Perfs:  
**INVOICED**  
DATE 3/25/10  
INV. NO. 2010060995  
RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 01 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: LANDOWNER (FRANK GREEN P.O. BOX 235, CHAUTAUQUA KS. 67334) PLUGGED WELL SO PLUGGING FEES SHOULD BE WAIVED.

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)