

# 54.76

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-31248-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 24-34S-13E  
3400 feet from S Section Line, 2180 feet from E Section Line  
Lease Name: W MICHAEL Well #: B3-24  
County: MONTGOMERY Total Vertical Depth: 1685 feet

Operator License No.: 33074  
Op Name: DART CHEROKEE BASIN OPERATING  
Address: 600 DART RD PO BOX 177  
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	40		8 SX CEMENT
PROD	4.5	1679		1679 SX CEMENT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2010 10:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: run tubing to TD and circulate cement from bottom to top

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2010 11:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Operator ran 55 joints of 2 3/8" tubing in hole and circulated 98 sacks of cement. Pulled 30 joints of pipe and circulated 28 more sacks of cement to surface. Pulled 2 3/8" and topped well off. A total of 126 sacks of cement were used to plug this well.

Perfs: \_\_\_\_\_

RECEIVED  
MAR 31 2010 DAS  
KCC Chanute Dist. #3

INVOICED  
DATE 4/12/10  
INV. NO. 2010061042

RECEIVED  
APR 09 2010  
KCC WICHITA

Remarks: TUBING  
Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)