

\$120.15

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05568-00-00
Spot: E2NENW Sec/Twnshp/Rge: 31-11S-17W
4620 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MARSHALL A Well #: 14
County: ELLIS Total Vertical Depth: 3697 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1391	0	400 SX
PROD	5.5	3697	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2010 8:00 AM
Plug Co. License No.: 5214 Plug Co. Name: LARIO OIL & GAS COMPANY
Proposal Rcvd. from: DAVID L. JENSEN Company: LARIO OIL & GAS COMPANY Phone: (785) 625-5023

Proposed Plugging Method: Ordered 785 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel. PBTB 3685'. Casing leaks 2404'-3434' and 3113'-3144'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2010 2:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Tiger Wireline Service perferd at 1850' and 1300'. Lario RIH with tubing to 3491'. Allied rigged to tubing and pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix 4% gel with 200# hulls mixed in. Pulled tubing to 1850'. Allied rigged to tubing and pumped 535 sxs cement with 300# hulls mixed in. Pulled tubing to 800'. Ordered an additional 200 sxs cement. Rigged to tubing and pumped 200 sxs cement to circulate cement out 8 5/8" casing - shut in. Cement circulated out 5 1/2" casing. Pulled tubing - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3671	3674		
3654	3659		

INVOICED

DATE 4/12/10
INV. NO. 2010061044

RECEIVED
APR 09 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #36355.

KCC WICHITA

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

CM

LARIO OIL & GAS CO

#11 MARSHALL

31-11-17W
GE2 NE NW

ELLIS County

Contr

E 2125

Comm 2-3-44

Comp 3-1-44

IP


196 BOPD

4% WTR

Tops	Depth	Datum
ANH	1360	
LANS	3366	
B/KC	3613	
SIMP	3619	
ARB	3647	
TD	3695	

Casing
8" 1391
5" 3695

Perf 11/3671-74: A/500
Swb 26 BOPH/12 hrs
Pmp 22 BOPH & 4% wtr



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS