

#122.69

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25958-00-00  
Spot: NWSWNESW Sec/Twnshp/Rge: 4-15S-19W  
1750 feet from S Section Line, 1550 feet from W Section Line  
Lease Name: YARNELL Well #: 1  
County: ELLIS Total Vertical Depth: 3775 feet

Operator License No.: 4787  
Op Name: TDI, INC.  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2010 8:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: TOM ENGEL Company: TDI, INC. Phone: (785) 628-2593

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 03/30/2010 9:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:  
1st. Plug at 3698' w/25 sxs.  
2nd. Plug at 1350' w/25 sxs.  
3rd. Plug at 600' w/80 sxs.  
4th. Plug at 250' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:  
**INVOICED**  
DATE 4/2/10  
INV. NO. 200061047

**RECEIVED**  
**APR 09 2010**  
**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: DP

District: 04 Signed Case Morris  
(TECHNICIAN)

APR 07 2010