

#115.83

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22661-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 13-11S-19W
2021 feet from S Section Line, 3251 feet from E Section Line
Lease Name: ALLISON Well #: 1
County: ELLIS Total Vertical Depth: 3564 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	246	0	200 SX CMT
PROD	4.5	3560	0	75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2010 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 520 sxs 60/40 pozmix - 4% gel - 700# hulls.
PBTD 3526'. Perfs-Lans 3426' - 3431'.
2 3/8" tubing stuck in the hole at 3425' to surface.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2010 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Oil Well Cementing rigged to tubing and pumped 50 sxs 60/0 pozmix - 4% gel - displaced to 1850'.
Perf Tech RIH and perfed two shot holes at 1850' - 1305' - 650' - 200'.
Quality Oil Well Cementing rigged back onto tubing and pumped 250 sxs cement with 200# hulls - no circulation.
Left set 20 minutes - pumped an additional 20 sxs cement - well went on vacuum
Left set two hours until new cement truck arrived.
Rigged to 2 3/8" tubing - pumped an additional 50 sxs cement with 200# hulls.
Max. P.S.I. 600#. S.I.P. 300#.
Rigged to backside of tubing - instant pressure.
Rigged to 8 5/8" casing - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3208	3440		
3184	3200		

INVOICED
DATE 4/12/10
INV. NO. 2010061049

RECEIVED
APR 09 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3580.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

APR 06 2010

PETRO-DYNAMICS, LTD.

REPLACEMENT CARD

555 N. WOODLAWN, BLDG. 1, #207

#1 ALLISON

13-11-19W

WICHITA, KS 67208

C NE SW

CONTR KANDRILCO, LTD.

CTY ELLIS

GEOL

FIELD

WC (3/8 E OF SOLOMON;
SEP BY DRY HOLES)

ELV 1952 KB SPD 11/6/81

CARD ISSUED

10/7/82

IP TEMP ABD

API 15-051-22,661

SMP	Tops	Depth/Datum	
HEEB		3168-1216	8.58 246200SX 4 1/2 355975SX
TOR		3184-1232	DST (1) 3172-3219 (LANS) / 30-30-30-30, REC 62 MW, SIP 189-108#, FP 54-54 / 54-54#
LANS A		3208-1256	DST (2) 3280-3350 (LANS) / 30-60-30-60, REC 181 MW, SIP 721-773#, FP 70-93 / 100-108#
LANS B		3241-1289	DST (3) 3355-3380 (LANS) / 30-60-30-60, REC 7 OSM, SIP 131-189#, FP 15-15 / 23-23#
LANS D		3282-1330	DST (4) 3355-3405 (LANS) / 30-60-30-60, REC 8 MW, SIP 256-100#, FP 31-31 / 31-31#
LANS H		3343-1391	DST (5) 3414-3441 (LANS) MIS-RUN
LANS I		3365-1413	10/DST (6) 3435-3525 (ARB) / 30-30-30-30, REC 2887 SO, SPK SW, SIP 1124-1140#, FP 436-956 / 1053-1156#
LANS J		3381-1429	MICR-00, PF (LANS) 3426-3431 W/4 SPF, AC 250G, SION, SWB 2.88 BF (35% O), RE-AC 500G, SWB 10, GOPH, SION, AC 1500G, SWB BK LD, W/SSD, PROD NON-COMMERCIAL, TEMP ABD
LANS K (SWOPE)		3404-1452	
LANS L (HERTHA)		3426-1474	
ARB		3518-1566	
PBTD		3526-1574	
TD		3564-1612	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INFO RELEASED: 12/9/82 - WAS OIL WELL - TIGHT HOLE