

# 114.40

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23626-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 13-11S-19W  
3639 feet from S Section Line, 459 feet from E Section Line  
Lease Name: ALLISON B Well #: 5  
County: ELLIS Total Vertical Depth: 3520 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1242	0	450 X
PROD	5.5	3517	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2010 11:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed	Ordered 675 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plugging	Operator elected all cement plug.
Method:	Could not pull tubing - turned off at 2305' - could not get back in due to sand coming in. Perf Tech perfed at 1200'. Plugged due to lease work-up and TA status.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2010 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Oil Well Cementing rigged to tubing at 2305' - pumped 150 sxs 60/40 pozmix - 4% gel with no hulls mixed in.  
Pulled tubing to 1100'. Perf Tech ran in through tubing and perfed at 1200'.  
Klima Well Service ran back into the hole to 1900'.  
Quality Oil Well rigged to tubing and pumped 60 sxs cement with 200# hulls to circulate cement up 5 1/2" casing.  
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 20 sxs cement with 300# P.S.I.  
Blew small hole in 5 1/2" casing. Rigged to 8 5/8" casing and pumped 5 sxs cement - circulated out 5 1/2" casing.  
Topped off 5 1/2" casing. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3202	3454		LKC

INVOICED  
DATE 4/12/10  
INV. NO. 2010061049

RECEIVED  
APR 09 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3936.

KCC WICHITA

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

APR 06 2010

SEAHAWK OIL INTERNATIONAL, INC.  
660 NEWPORT CENTER DR. ST.  
NEWPORT BEACH, CA 92660

#5 ALISON


13-11-19W  
NE SE NE

CONTR KANDRILCO, INC.

CTY ELLIS

GEOL \_\_\_\_\_

FIELD COCHRAN WEST



ELV 1913 KB SPD 9/22/83 CARD ISSUED 7/26/84 IP P 13 BOPD, TR WTR  
1905 GL LKC 3202-3454  
API 15-051-23,626

LOG	Tops .....	Depth/Datum	
			8 5/8 " 1242.86, 5 1/2 " 3517
			NO DSTS
			MICT - CO, PF (LKC) 3202-3454 OA, AC 5000G, SWB DWN, SO,
			POP, P 13 BOPD, TR WTR, 10/2/83
HEEB	.....	3127-1214	
LANS	.....	3167-1254	
BKC	.....	3407-1494	
ARB	.....	3495-1582	
RTD	.....	3520-1607	

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS