

#117

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23015-00-00  
Spot: NENWNWNE Sec/Twnshp/Rge: 18-11S-18W  
330 feet from N Section Line, 2145 feet from E Section Line  
Lease Name: FRISBIE B Well #: 1  
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	330	0	175 SX
PROD	5.5	3595	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2010 9:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.  
Well was flowing.  
Lease worked up by Pat Staab.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/26/2010 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:  
Perf Tech perfed at 1650' - 1250' - 300'.  
Klima Well Service RIH with tubing to 3223'.  
Quality Oil Well Service rigged to tubing and pumped 9 sxs gel - followed with 100 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.  
Pulled tubing to 1650'. Quality rigged to tubing and pumped 170 sxs cement with 200# hulls mixed in to circulate cement up 5 1/2" casing.  
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 12 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Pulled bull plug off 8 5/8". Cement full in casing - visual check.  
Pump truck plugged off pumping gel spacer.

**Perfs:**

Top	Bot	Thru	Comments
3060	3380		Shaw & LKC

**INVOICED**  
DATE 4/12/10  
INV. NO. 2010061049

**RECEIVED**  
**APR 09 2010**

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3966.  
Plugged through: TBG

**KCC WICHITA**

District: 04

Signed *Pat Staab*  
(TECHNICIAN) CM

APR 05 2010

ROBERT R. PRICE OPERATING, INC. #1 "B" FRISBIE 18-11-18W  
 P.O. BOX 45442 TULSA, OK 74145 330' FNL &  
 CONTR RANGER ORLG. CO. CTY ELLIS 496' FWL, NW NE

GEOL \_\_\_\_\_ FIELD COCHRAN WEST

E 1910 KB CM 6/24/82 CARD ISSUED 9/2/82 IP P 8.80 & 110 BWPD  
 1905 GL  
 API 15-051-23,015 SHAW & LKC  
 3060-3380 OA

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1239	+ 671
ANH		2892	- 982
HEEB		3116	-1205
TOR		3135	-1225
LANS		3157	-1247
BKC		3383	-1473
CONG		3420	-1510
ARB		3487	-1577
PBTD		3534	-1624
LTD		3585	-1675
RTD		3600	-1690

8-5/8" 330/175sx, 5 1/2" 3595/200sx

NO DST'S  
 MICT - CO. PF (ARB) INTV NA W 1 SPF. ACIDIZED. TSTO NON-COMMER-  
 CIAL. PF (SHAW & LKC) 3060-3380 OA W 1 SPF. SELECTIVE INTV'S NA).  
 AC 16.000G. SWB DWN W GSO. POP. P 9.80 & 110 BWPD (GR 29.6'). 8  
 6 82. COMMINGLED - NO OTHER INFO TO BE RELEASED AT PRESENT -  
 WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP 9 2 82

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS