

#112.81

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22247-00-00  
Spot: E2E2SE Sec/Twnshp/Rge: 12-11S-19W  
1320 feet from S Section Line, 330 feet from E Section Line  
Lease Name: GLADYS Well #: 6  
County: ELLIS Total Vertical Depth: 3471 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	168	0	135 SX
PROD	4.5	3470	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/24/2010 12:30 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 500# hulls - 7 sxs gel.  
Lans 3210'-3250'.  
Lease worked up by Pat Staab.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/24/2010 4:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1850' - 1300' - 650'.  
Klima Well Service RIH with tubing to 3125'.  
Quality Oil Well rigged to tubing and pumped 7 sxs gel - followed with 40 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.  
Pulled tubing to 1850'. Quality Oil Well rigged to tubing and pumped 85 sxs cement with 250# hulls to circulate cement to surface.  
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 15 sxs cement.  
Max. P.S.I. 600#. S.I.P. 600#.  
Rigged to 8 5/8" casing - pumped 5 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

INVOICED  
DATE 4/12/10  
INV. NO. 2010061049

RECEIVED  
APR 09 2010  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3579.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN) CM

JOHN B COLLINS  
HAYS KS

site: 7 N & 3/4 E OF HYACINTH KS  
contr: DREILING OIL  
ged: LAWRENCE F GRAY

# 6 GLADYS

12-11S-19W  
C E/2 E/2 SE


date 01/19/81

spc  
date 01/09/81

drig  
comp 01/14/81

city: ELLIS  
field: COCHRAN WEST

API 15-051-22247



ELV:	depth/datum
1947 KB, 1942 GL SMP	1294 + 653
tops	2943 - 996
SC	3166 - 1219
TOP	3183 - 1236
HEEB	3206 - 1259
TOR	3441 - 1494
LANS	3471 - 1524
BKC	
RTD	
NO LOG	

**IP status:**

**OIL, LKC, INTV NA**, 09/01/81  
INFO RELEASED: 2/16/98 - WAS OIL WELL - TEMP  
COMP

CSG: 8-5/8" 168 / 135 SX, 4-1/2" 3470 / 150 SX  
NO CORES  
DST (1) 3210-3250 (LANS), / 30-45-30-45, REC 80' OCM

ISIP 643# FSIP 429# IFP 53# -85# FFP 107# -107# IHP  
1817# FHP 1817#  
MICT - CO, PF (LANS) INTV NA, AC 14,000 GAL, SO,  
POP, OIL WELL (POTENTIAL NOT RPTD), 9/1/81 - NO

OTHER INFO RELEASED BY OPERATOR OR ON KCC  
RECORDS; ALL REQUESTS FOR INFO DENIED

COPYRIGHT 1988  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS