

115-77

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19020-00-00
Spot: SESENW Sec/Twnshp/Rge: 18-15S-17W
2948 feet from S Section Line, 3055 feet from E Section Line
Lease Name: LEIKER Well #: 1
County: ELLIS Total Vertical Depth: 3562 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1155	0	w/475 sxs cmt
PROD	5.5	3556	0	w/75 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2010 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 850 sxs 60/40 pozmix - 4% gel - 1500# hulls - 14 sxs gel.
Casing leaks.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2010 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:
Perf Tech shot two hole perfs at 1650' and 1100'.
Klima Well Service RIH with tubing to 3312'.
Quality Oil Well Cementing rigged to tubing and pumped 14 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 350# hulls mixed in.
Klima Well Service pulled tubing to 1650'.
Quality Oil Well rigged to tubing and pumped 550 sxs cement with 650# hulls mixed in.
Cement did not circulate up 5 1/2" casing or 8 5/8" casing.
Ordered an additional 150 sxs 60/40 pozmix.
Pulled tubing to 800' - pumped 150 sxs cement with 500# hulls mixed in - cement did not circulate.
Operator ordered an additional 100 sxs cement.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 80 sxs cement to circulate 8 5/8" casing - shut in.
Squeezed 20 sxs cement into 5 1/2" casing .
Max. P.S.I. 50#. S.I.P. 20#.

Perfs:

Top	Bot	Thru	Comments
3559	3562		

INVOICED
DATE 4/12/10
INV. NO. 2010061049

RECEIVED
APR 09 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3807.

KCC WICHITA

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)


CM

APR 07 2010

LINDAS OIL #1 LEIKER 18-15-17W 34
 SE SE NW
 Contr. LINDAS OIL COMPANY ELLIS County
 E 1991 Comm. Comp. 11-21-52 IP 50 BOPD

Tops	Depth	Datum
HEEB	3229	-1238
LANS	3279	-1288
B/KC	3488	-1497
ARB	3555	-1991
T.D.	3562	-1571

Casing
 8" 1150
 5" 3556
 DP: CO: DD 3559, 1 BOPH, ACID
 1000: SWB 1.67 BO: DD 3562
 SWB 15 BO/4½ HRS: PB 3557



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS