

# 116.51

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03113-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 18-15S-17W  
336 feet from S Section Line, 1752 feet from E Section Line  
Lease Name: STECKLEIN Well #: 4  
County: ELLIS Total Vertical Depth: 3585 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1149	0	475 SX
PROD	5.5	3579	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2010 10:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 850 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.  
Casing leaks. PBTB 3470'.  
*Lease worked up by Pat Staab*

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2010 4:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed two shots at 1650' and 1100'.  
Klima Well Service RIH with tubing to 3312'.  
Quality Oil Well Cementing rigged to tubing and pumped 14 sxs gel followed with 50 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.  
Klima Well Service pulled tubing to 1650'.  
Quality Oil Well Cementing rigged to tubing and pumped 280 sxs cement with 250# hulls to circulate cement up 5 1/2" casing.  
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 320 sxs cement - cement did not circulate out 8 5/8" casing.  
Operator ordered an additional 200 sxs cement.  
Rigged back onto 5 1/2" casing - pumped 50 sxs cement to circulate cement up 8 5/8" casing - shut in - pumped 5 sxs cement to 150# P.S.I. Blew rubber ring out of head. 5 1/2" casing full.

**Perfs:**

Top	Bot	Thru	Comments
3550	3558		
3302	3305		

**INVOICED**  
DATE 4/12/10  
INV. NO. 2010061049

**RECEIVED**  
**APR 09 2010**  
**KCC WICHITA**

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3806.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Staab*  
(TECHNICIAN)

CM

APR 06 2010

JOHN LINDAS OIL

#4

STECKLINE

18-15-17W  
SE SW SE

Contr. JOHN LINDAS OIL

ELLIS

County

E. 1995 R.B. Comm. 7-23-53 Comp. 10-9-53 IP 75 BOPD

Tops	Depth	Datum
ANH	1143	852
HEEB	3231	=1236
TOR	3250	=1255
LANS	3280	=1285
CONG	3552	=1557
ARB	3579	=1584
TD	3585	=1590

Casing

8" 1149

5" 3579

DST 3282-3330/

1 HR, 1260'

FL, 90' MDY OIL

BHP 105#:

CO 3585: AGID 500: WTR: PB

3570: PERF 3550-58: SSO:

PB 3450: PERF 3302-05:

WHEATLAND POOL 20 BOPD:


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS