


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Greeley County, Sec. 36 Twp. 20S. Rge. 11W (EX) (W)
Location as "NE/CNW4SW4" or footage from lines 1450' FSL and 1450' FEL
Lease Owner Dorchester Exploration, Inc.
Lease Name Beard #1 Well No. 1
Office Address 1204 Vaughn Building, Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 26, 1973 19
Application for plugging filed February 24, 1973 19
Application for plugging approved February 24, 1973 19
Plugging commenced 6:00 AM, February 26, 1973 19
Plugging completed 8:00 AM, February 26, 1973 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2780' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 10 3/4" | 337' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Plug #1 - 140 cu. ft. thru D.P. at shot 1175'.
Plug #2 - 40 cu. ft. thru D.P. at 340'.
Plug #3 - 20 cu. ft. from 40' to Base of Cellar.


RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
Bernard Laudermilk (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Bernard Laudermilk
Bernard Laudermilk, Vice President
P. O. Box 129, Sterling, Kansas 67579
(Address)



Subscribed and Sworn to before me this 5th day of March, 19 73
Charles M. Hall Notary Public.
My Commission Expires Jan. 6, 1974

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- BEARD #1
Located: Section 36-20S-41W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 21, 1973
COMPLETED: February 26, 1973

TOTAL DEPTH: 2780'

| <u>LOG</u> | <u>CASING RECORD</u> |
|----------------------------|--|
| 0 - 347 Shale and Garvel | Ran 10 joints 10 3/4" casing, 337' cemented with 150 sacks Howco Lite, 2% cc, followed with 150 sacks Common, 3% cc. Plug down at 10:45 PM, 2-21-73. |
| 347 - 2352 Shale and Sand | |
| 2352 - 2371 Anhydrite | |
| 2371 - 2425 Shale and Sand | |
| 2425 - 2550 Shale and Lime | |
| 2550 - 2780 Shale and Sand | |
| | Plugged. |

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1973
CONSERVATION DIVISION
Wichita, Kansas