

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-20499-00-00

API NUMBER 11-16-71
 LEASE NAME Kno11
 WELL NUMBER 2
 C. NW SW NE _____ Ft. from S Section Line
_____ Ft. from E Section Line
 SEC. 22 TWP. 10 RGE. 25 (E) or (W)
 COUNTY Graham
 Date Well Completed 11-16-71
 Plugging Commenced 1-15-90
 Plugging Completed 1-16-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren Corp.
 ADDRESS Box 723 Hays, Kansas 67601
 PHONE# (913) 682 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-16-90 (date)
 by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____
 Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1990
 CONSERVATION DIVISION
 Wichita, Kansas

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	210	8 5/8		
	Casing	0	4049	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed from feet to feet each set.
Rig up Mercury and perf. 2 shots at 1330'. Run openended tubing to 3932'. Rig up BJ Titan pump 100 sks. 65/35 10% gel 2% A? 100# hulls. Pull tubing to 2022' pump 100 sks. cement 100# hulls. Hook to 8 5/8 pump 100 sks. 100# hulls. Shut in 500#. Hook to 5 1/2 casing pump 25 sks. cement

Shut in with _____ (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364
 Address Box 723 Hays, Kansas 67601 (BJ Titan cementer)

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

ROSEMARY SMITH
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXP. MAY 1, 1991

(Signature) Ted Crawford
 (Address) Box 723 Hays, Ks 67601

SUBSCRIBED AND SWORN TO before me this 17 day of January, 19 90

Rosemary Smith
 Notary Public

My Commission Expires: 5/1/1991