

15-065-20243-00-00

API NUMBER _____

LEASE NAME Knoll

WELL NUMBER 1

NW NW SE _____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 22 TWP. 10 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 1-15-90

Plugging Completed 1-15-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE#(913 628 6101) OPERATORS LICENSE NO. 5364

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-15-90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4017

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0		8 5/8		
	Casing	0	4107	4 1/2		

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1990
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Got on plug at 3595'. Released. Rig up Mercury Wireline and perf. 2 shots at 1330'. TIH with opened tubing to 3932'. Rig up BJ Titan pump 65 sks. 65/35 10% g31 2% A 2 cement with 100# hulls. Pull 62 joints to 2022' pump 80 sks. cement with 150# hulls. TOH with tbq. Hook up 8 5/8" pump 100 sks. cement 150# hulls. Shut in 400#. Pump 15 sks. into 4 1/2 casing and shut in with 800#.
 (Additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601 (BJ Titan cementer)

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601

17 day of January, 19 90

Rosemary Smith
 Notary Public

ROSEMARY SMITH
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXP. MAY 1, 1991

My Commission Expires: 5/1/1991