

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-065-20,424-00-01

LEASE NAME Knoll

WELL NUMBER #3

1320' Ft. from S Section Line

1650' Ft. from E Section Line

SEC. 22 TWP. 10 SRGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 06/18/02

Plugging Completed 06/18/02

RECEIVED
6-26-2002
JUN 26 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Richlan Drilling

ADDRESS 598 2nd Avenue, Beaver, KS 67525

PHONE (620) 587-3605 OPERATORS LICENSE NO. 31086

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 17, 2002 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top 1830' Bottom 1892' T.D. 1892'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	204'	8-5/8"	204'	0'
	Production	0'	1892'	4-1/2"	1892'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Note: 2-3/8" tbq is cemented in hole. Rig up and tie on to 2-3/8" tbq. Pump 45 sx 60/40 poz, 10% gel cement. Pressured up to 1000#. Tied on to 8-5/8" pipe. Pump 50 sx 60/40 poz, 10% gel cement. Shut in pressure @ 100#. Tied on to 4-1/2" casing. Pressured up to 700# - held. Well plugged. Rig down and move off.

Name of Plugging Contractor D.S. & W. Well Servicine, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Richlan Drilling

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 25th day of June, 2002

Karen J. Mitchell
Notary Public

My Commission Expires: June 13, 2006

OR