

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-065-03153-0000  
 API NUMBER 5-26-60

LEASE NAME Elrick Unit

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 2-1  
4290 ANB KCC  
~~495~~ Ft. from S Section Line  
~~990~~ 4950 Ft. from E Section Line

LEASE OPERATOR Citation Oil & Gas Corporation

SEC. 14 TWP. 10S RGE. 25 (E) or (W)

ADDRESS 8223 Willow Place South Ste 250 Houston, TX 77070-5623

COUNTY Graham

PHONE# (713) 469-9664 OPERATORS LICENSE NO. 03553

Date Well Completed 5-26-60

Character of Well Oil

Plugging Commenced 10-10-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-11-91

The plugging proposal was approved on August 14, 1991 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? submitted w/CP-1

Producing Formation LKC Toronto Depth to Top 3756' Bottom 3970' T.D. 4230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3756'	3773'	8 5/8"	122'	0
LKC	Oil	3773'	3970'	5 1/2"	4015'	0

OCT 25 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RIH w/tbg to 3900' spotted 90 sx cmt w/ 400 lbs hulls. Pulled up hole to 2122' & perf'd 3 shots @ 2150'. Spotted 100 sx cmt w/ 200 hulls. Pulled up hole to 1240 & perf'd 3 shots. Spotted 60 sx cmt. Circulated cmt to surface. Squeezed 50 sx cmt down 5 1/2" csg. Hooked to 8 5/8" csg & squeezed 75 sx cmt w/ 50 lbs. hulls. Cmt was 60/40 Poz 400 sx w/ 10% gel, 1/4 lb F locele per sack, + 700 lbs. hulls. All work witnessed and approved by KCC Representative: Dennis Hamil.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Leon's Cable Tool Rig/ Citation License No. unknown

Address 4848 S. W. 36TH Street Oklahoma City, OK 73179


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corporation

STATE OF Texas COUNTY OF Harris, ss.

Sharon E Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon E Ward  
 (Address) 8223 Willow Place South Ste 250 Houston, TX 77070

SUBSCRIBED AND SWORN TO before me this 22 day of October, 1991



Renee Harrell  
 Notary Public

Expires: 3-2-95