

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM

County. Sec. 14 Twp. 10 Rge. 25 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE NW SW

Lease Owner C-G DRILLING CO.

Lease Name KNOLL "A" Well No. 1

Office Address 107 RULE BUILDING, WICHITA, KANSAS 67202

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JULY 9, 19 66

Application for plugging filed JULY 9, 19 66

Application for plugging approved JULY 9, 19 66

Plugging commenced JULY 9, 19 66

Plugging completed JULY 9, 19 66

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, MORELAND, KANSAS

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4025 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209.59	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD TO 540'. SET PLUG. PUT IN 20 SX CEMENT. FILLED WITH HEAVY MUD TO 210'. SET PLUG. PUT IN 20 SX CEMENT AND 1/2 SACK HULLS. FILLED WITH HEAVY MUD UP TO 40'. SET PLUG. FILLED TO TOP WITH 10 SX CEMENT AND 1/2 SACK HULLS.

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1966

Name of Plugging Contractor C-G DRILLING CO.
Address 107 RULE BUILDING, WICHITA 2, KANSAS


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. G. F. Galloway

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. GALLOWAY 107 RULE BUILDING (Address)

Subscribed and sworn to before me this 11th day of JULY, 19 66

My commission expires 5/20/67 VICKY JACOBS Notary Public.



WELL LOG

OPERATOR: C-G DRILLING CO.
 WELL NAME: KNOLL "A" #1 LOCATION: S E NW SW 14-10-25W
 COUNTY: GRAHAM COUNTY STATE: KANSAS
 WELL COMMENCED: 6-30-66 WELL COMPLETED: 7-9-66
 ELEVATION: 2479 KB TOTAL DEPTH: 4025'
 PRODUCTION: Dry & Abandoned RIG NO: #1
 CASING - 8-5/8": 6 its. 209.59' w/140 sx QUIKSET 20 lb.
 5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	209	SHALE & SAND	500 1 1/2°	
209	855	SHALE	710 3/4°	
855	1695	SHALE & SAND	1100 1°	
1695	1800	SAND	1265 1/4°	
1800	2117	SAND & SHALE	1500 1/2°	
2117	2150	ANHYDRITE	2000 3/4°	
2150	2410	SHALE & SHELLS	2500 3/4°	
2410	3778	LIME & SHALE	3000 3/4°	DST #1 3771-3778
3778	4025'	LIME		DST #2 3827-3843 DST #3 3934-3952

RECEIVED
STATE COMMISSION COMMISSIONER

JUL 15 1966

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, This 11th day of JULY, 1966.

My comm. exp: May 20, 1967

Vicky Jacobs
Vicky Jacobs - Notary Public

