

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY GRAHAM SEC. 14 TWP. 10s RGE. 25w E/W  
Location as in quarters or footage from lines:  
NW-SW-NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner TENNECO OIL COMPANY  
Lease Name ELRICK Well No. 1-1  
Office Address 7301 NW EXPRESSWAY, P.O. BOX 25420, OKLAHOMA CITY, OK  
Character of Well (Completed as Oil, Gas or Dry Hole): OIL 73125  
Date Well Completed 6-28-60  
Application for plugging filed 11-26-86  
Plugging commenced 1-19-87  
Plugging completed 1-22-87  
Reason for abandonment of well or producing formation \_\_\_\_\_

NON-COMMERCIAL  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GIL BALTHAZOR  
Producing formation LKC Depth to top 3758 bottom 3972 T.D. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
LKC	oil & water	3758	3972	5 1/2	4019	NONE
				8 5/8	220	NONE
FLUID LEVEL	375'					

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. Run gauge ring and junk basket to 2642. Set C.I.B.P.  
@ 2640'. Spot 5 sks cement. Perforated 2 holes @ 2150', 2 holes @ 1260'. 50 sks  
60/40 poz., 3 sks hulls, 150 sks 60/40 poz. Max pressure: 1200#, S.I.P. 800#.  
50 sks down 8 5/8. Max pressure: 300, S.I.P.: 100#.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PRODUCTION DRILLING, INC.

STATE OF KANSAS COUNTY OF ELLIS, ss.  
LARRY L. PATTERSON (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P.O. BOX 680 HAYS, KS 67601  
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of Feb, 19 87

[Signature]  
Notary Public.

My Commission expires: 30 July 1987



RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 1987  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-01919-0000


WELL LOG BUREAU- KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- HERNDON DRILLING COMPANY  
Farm- Knoll "C" No. 1

SEC. 14 T. 10 R. 25W  
NW SW NW

Total Depth. 4020'  
Comm. 6-17-60 Comp. 6-28-60  
Shot or Treated.  
Contractor. Herndon Drilling Co.  
Issued. 9-24-60

County Graham  
KANSAS



CASING:

8 5/8" @ 220.54' w/160 sks. cem.  
5 1/2" @ 4018.78' w/100 sks. cem.

Elevation. 2492'

Production. 10 BOPD

Figures Indicate Bottom of Formations.

surface hole	220
shale & shells	1925
shale & lime	2140
Anhydrite	2206
shale & shells	2448
shale & lime	3170
lime	3265
lime & shale	3790
lime	4020
Total Depth	

SCOUT TOPS:

Heebner	3739
Toronto	3760
Lansing	3778