

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-065-03154-0000  
 API NUMBER 8-25-60

LEASE NAME Elrick Unit

WELL NUMBER 2-2

4950' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 14 TWP. 10S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 8-25-60

Plugging Commenced 10-16-91

Plugging Completed 10-18-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corporation

ADDRESS 8223 Willow Place South Ste 250 Houston, TX 77070-5623

PHONE# (713) 469-9664 OPERATORS LICENSE NO. 03533

Character of Well Oil RT KCC

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 14, 1991 (date)

by David P. Williams/Don Butcher witnessed by Dennis Hamil (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? submitted w/CP-1

Producing Formation Toronto/LKC Depth to Top 3754' Bottom 3998' T.D. 4235'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED  
OCT 25 1991  
COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3754'	3764'	8 5/8"	92'	0
LKC	Oil	3764'	3977'	5 1/2"	4014'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set. RIH to 3693' drld. CIBP to 3963'. Filled 5 1/2" csg w/mud. At 3905' pumped 90 sx cmt w/400# hulls. Perf'd 3 holes at 2150'. Pumped 100 sx cmt. Perf'd 3 holes at 1250'. Pumped 25 sx cmt + 200# hulls to surface. Rigged up to csg and pumped 75 sx cmt. Pumped 125 sx cmt. + 100# hulls down 8 5/8" csg. Well plugged and abandoned on 10-18-91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Leon's Cable Tool Rig/Citation License No. unknown

Address 4848 S.W. 36th Street Oklahoma City, OK 73179

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corporation


STATE OF Texas COUNTY OF Harris, ss.

Sharon E. Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon E. Ward  
 77070-5623  
 (Address) 8223 Willow Place South Ste 250 Houston, TX

SUBSCRIBED AND SWORN TO before me this 22 day of October, 1991

Renee Harrell  
 Notary Public



RENEE HARRELL  
 MY COMMISSION EXPIRES: 3-2-95