

15-065-01911-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 9/11/62

LEASE NAME Frank (also known as East Elrick #3-1)  
WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line  
1650 Ft. from E Section Line

LEASE OPERATOR KNIGHTON OIL COMPANY, INC.  
710 Petroleum Bldg.  
ADDRESS Wichita, Ks. 67202

SEC. 11 TWP. 10S RGE. 25 XK or (W)  
COUNTY Graham

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Date Well Completed 9/11/62

Character of Well SWD

Plugging Commenced 7/30/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/30/91

The plugging proposal was approved on 6/27/91 (date)  
by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Lansing/KC Depth to Top 3758 Bottom 3960 T.D. 3960

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE OF

COMMISSION

9-13-1991

Formation	Content	From	To	Size	Put in	Pulled out
		SURF.	205	8 5/8"	205'	None
		SURF.	3955	4 1/2"	3955'	None

SEP 13 1991

WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 50 sacks common cement @3702, 100 sacks 65/35 Pozmix, 6% Gel @2950, 65 sacks 65/35 Pozmix, 6% Gel @ 1000 and circulate to surface, pump 50 sacks 65/35 Pozmix into 4 1/2" casing @500psi. Pumped 150 sacks plus hulls into 8 5/8" @150psi and shut well in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service License No. 6426

Address P.O. Bos 426, Victoria, Ks. 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Earl M. Knighton, Jr. (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.

710 Petroleum Bldg.


(Address) Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 6 th day of September, 19 91

Sarah A. Simon

Notary Public  
Sarah A. Simon

My Commission Expires: 12/11/93



**COPY**


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
508 East Murdock, Wichita, Kansas

Company- **KIMBARK EXPLORATION CO.**  
Farm- **Frank** No. **1**

SEC. **11** T. **10** R. **25W**  
**NE NW SE**

Total Depth. **3959'**  
Comm. **10-17-61** Comp. **10-29-61**  
Shot or Treated.  
Contractor.  
Issued. **3-3-62**

County **Graham**  
**KANSAS**



CASING:  
**8 5/8" 205'** cem w/165 sx.  
**4 1/2" 3960'**

Elevation. **2477'**

Production. **90 BOPD**

Figures indicate Bottom of Formations.

sand & shale	210
shale	2075
shale & lime	2825
lime	2945
shale & lime	3105
lime	3290
lime & shale	3579
lime	3958 RTD
lime	3959
Total Depth	
TOPS: SCOUT	
Anhydrite	2140
Heebner	3720
Toronto	3740
Lansing	3758

**RECEIVED**  
STATE CORPORATION COMMISSION  
**9-13-1991**  
**SEP 13 1991**  
CONSERVATION DIVISION  
Wichita, Kansas