

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11/01/62

LEASE NAME Rome

WELL NUMBER 6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 11TWP. 10SRGE. 25 ~~XXX~~(W)

LEASE OPERATOR Knighton Oil Company, Inc.

COUNTY Graham

ADDRESS 710 Petroleum Bldg., Wichita, Kansas 67202

PHONE#(316) 264-7918 OPERATORS LICENSE NO. 5010

Date Well Completed 11/01/62

Character of Well Oil

Plugging Commenced 6/20/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/20/90

The plugging proposal was approved on 6/20/90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Lansing/KC Depth to Top 3788 Bottom 4022 r.D. 4025

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	Oil	Surf	199	8-5/8	199	None
		Surf	4023	4 1/2	4023	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 200 lbs hulls down tubing to 2100' followed by 100 sacks pozmix.
Pulled tubing and pumped 100 lbs hulls and 25 sacks cement on backside of
4 1/2" casing. Mixed and pumped 175 sacks inside 4 1/2" casing and shut well in
at 400 RPP. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service, Inc. License No. 6426

Address P. O. Box 426, Victoria, Kansas 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Sedgwick COUNTY OF Kansas, ss.

Earl M. Knighton, Jr. (Employee of Operator) ~~or xxxxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Earl M. Knighton Jr.


(Address) 710 Petroleum Bldg. Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 90

Sarah A. Simon

Notary Public Sarah A. Simon

Commission Expires: 12/11/93



15-065-01918-00-00
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,
 Wichita, Kansas


COPY

Company- **D. G. HANSEN**
 Farm- **Rome** No. **6**

SEC. **11** T. **10** R. **25W**
 N/2 N/2 NW

Total Depth. **4025'**
 Comm. **9-11-62** Comp. **9-21-62**
 Shot or Treated.
 Contractor. **C-G Drilling**
 Issued. **1-19-63**

County **Graham**
KANSAS



CASING:
 8 5/8" 199'
 4 1/2" 4023'

Elevation. **2507'** RB
 Production. **77 BOPD, NW**

Figures Indicate Bottom of Formations.

(All meas. taken from top of RB)

shale-sand	1015
shale	1200
sand	1290
shale	1730
sand	1920
shale	2050
red bed	2155
anhydrite	2198
shells-shale	2380
shale-shells	2585
shale-lime	2945
lime-shale	3285
shale-lime	3380
lime-shale	3500
shale-lime	3610
lime-shale	3765
lime	3836
lime-shale	3890
lime	3960
lime & shale	3980
lime	3985
lime-shale	4025
Total Depth	

TOPS: SCOUT	
Anhydrite	2155
Heebner	3751
Toronto	3775
Lansing	3788
Base Kansas City	4022

DST 3825-3836'
 DST 3941-3960'
 DST 3952-3980'

RECEIVED
 STATE CORPORATION COMMISSION
 8-30-1990
 AUG 30 1990

CONSERVATION DIVISION
 Wichita, Kansas

JOH