

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-01921-0000

API NUMBER 4/16/60

LEASE NAME Hanna

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 18 TWP. 10S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 4-16-60

Plugging Commenced 9-13-90

Plugging Completed 9-14-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Te-Pe Oil & Gas Company

ADDRESS P.O. Box 522, Canton, Kansas 67428

PHONE# (316) 628-4428 OPERATORS LICENSE NO. 5920

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-10-90 (date)

by Carl Goodrow (Hays) (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Kansas City Depth to Top 3840 Bottom 4071 T.D. 4090

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Kansas City	Oil & Water	169	GL	8-5/8	169	0
		4083	GL	5 1/2	4083	600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill hole with sand to 3704'. Dump 5 sacks of cement on bottom with bailer. Fill hole with fresh water. Perforate casing at 2175' and 1305'. Pump in 100 sacks 65/35 Pozmix 10% Gel. Shoot casing off at 600'. Pump 125 sacks 65/35 Pozmix 10% gel, 4 sacks bulls down casing and circulated cement to surface of 8-5/8 X 5 1/2 annulus. Pull casing. Fill 8-5/8 casing to surface with 25 sacks
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Well Service, Inc. License No. 3152

Address P.O. Box 115, Oberlin, Kansas 67749


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Te-Pe Oil & Gas Company

STATE OF Kansas COUNTY OF McPherson, ss.

Terry P. Bandy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
 STATE CORPORATION COMMISSION
 10-4-90

(Signature) Terry P. Bandy
 (Address) P.O. Box 522, Canton, Ks. 67428



Subscribed and sworn to before me this 1st day of October, 1990

CONSERVATION DIVISION
 Wichita, Kansas

(Signature) Cynthia G. Reimer
 Notary Public

My Commission Expires: May 15, 1994

of 65/35 Pozmix 10% gel. Shut in with 150# pressure on 8-5/8".