

15-065-00205-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County. Sec. 18 Twp. 10 Rge. 25 NE (W)

Location as "NE/CNW4SW4" or footage from lines. SE SE SW
Lease Owner Musgrove Petroleum Corporation, Inc.
Lease Name Wolf Well No. 1
Office Address 407 KFH Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 27 19 52
Application for plugging filed April 27 19 52
Application for plugging approved April 27 19 52
Plugging commenced April 27 19 52
Plugging completed April 27 19 52
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing				8-5/8"	204'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud.
Set first plug at 190' w/15 sx cement.
Set second plug at 40' w/10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation, Inc.
Address 407 KFH Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Gordon L. Koelling
407 KFH Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 52

My commission expires July 9, 1952.

Mary Lou Ryan
Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1952
CONSERVATION DIVISION
WICHITA, KANSAS

24-2675-S 2-52-20M
PLUGGING
FILE SEC 18 T 10 R 25W
BOOK PAGE 14 LINE 37

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Wolf #1
 LOCATION: SE SE SW Section 18-10S-25W
 Graham County, Kansas
 COMMENCED: April 11, 1952
 COMPLETED: April 27, 1952

0	40	Sand & clay
40	120	Sand & lime streaks
120	204	Shale
204	710	Blue shale
710	970	Gray shale & sand
970	1485	Shale, red bed, sand
1485	1875	Shale
1875	2155	Blue shale, red bed
2155	2220	Anhydrite
2220	2355	Shale & sand
2355	2555	Shale
2555	2810	Shale & shells
2810	2940	Shale & lime streaks
2940	3040	Shale & lime
3040	3120	Shale & lime streaks
3120	3220	Shaled lime
3220	3575	Lime & shale
3575	3658	Limed shale
3658	3766	Shale & lime
3766	3958	Lime
3958	4205	Lime & shale
4205	4260	Shale
4260	4348	Shale & lime
4348	4393	Shale, chert & lime
4393	4550	Lime & shale

Set 204' of 8-5/8" surface casing, cemented with 140 sacks.

Dry and Abandoned.

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Wolf #1, Section 18-10S-25W, Graham County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 2nd day of May, 1952.

Mary Lou [Signature]
 Notary Public

My commission expires July 9, 1952.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY - 3 1952
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 18 T 10 R 254
 BOOK PAGE 12 LINE 37

