

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM

County. Sec. 18 Twp. 10 Rge. 25 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE NW NE
Lease Owner DANE G HANSEN TR
Lease Name #4 HANNA "A" Well No. _____
Office Address BOX 187, LOGAN, KANSAS 67646
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPT. 13, 1968 19____
Application for plugging filed SEPT. 12, 1968 19____
Application for plugging approved SEPT. 12, 1968 19____
Plugging commenced SEPT. 12, 1968 19____
Plugging completed SEPT. 13, 1968 19____
Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, MORELAND, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4065' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	164.13'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 2551 feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD TO 1275'. SET
PLUG. PUT IN 100 SACKS CEMENT. FILLED
WITH HEAVY MUD TO 180'. SET PLUG. PUT
IN 20 SACKS CEMENT. FILLED WITH HEAVY
MUD UP TO 40'. SET PLUG. FILLED TO
TOP WITH 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING COMPANY
Address 1107 UNION NATIONAL BLDG. WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G F GALLOWAY (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) G F GALLOWAY
1107 UNION NATIONAL BLDG. (Address)

Sworn to before me this 18th day of SEPT., 1968



Phyllis Buchanan
PHYLLIS BUCHANAN
Notary Public.

W E L L L O G

OPERATOR: DANE G. HANSEN TR
 WELL NAME: #4 HANNA "A" LOCATION: NE NW NE SEC 18-10-25W
 COUNTY: GRAHAM COUNTY STATE: KANSAS
 WELL COMMENCED: SEPT. 6, 1968 WELL COMPLETED: SEPT. 13, 1968
 ELEVATION: 2551 KB TOTAL DEPTH: 4065'
 PRODUCTION: DRY & ABANDONED RIG NO: 1
 CASING - 8-5/8": 8 jts 164.13' W/130 SACKS QUICKSET
 5-1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
164	1055	SHALE & SAND	1/4° 500'	DST #1 3818-3850'
1055	1755	SHALE	3/4° 1500'	DST #2 3935-3980'
1750	1955	SAND	1° 1985'	
1955	2164	SHALE & RED BED	3/4° 2500'	
2164	2208	ANHYDRITE	3/4° 3180'	
2208	2485	SHALE		
2485	2785	SHALE & SHELLS		
2785	3775	LIME & SHALE		
3775	4065	LIME		

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 25 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By [Signature]

SUBSCRIBED AND SWORN TO, BEFORE ME, This 18th day of SEPT., 1968.

MY COMM. EXP. DEC. 7, 1971

[Signature]
 PHYLLIS BUCHANAN - NOTARY PUBLIC

