

15-065-20127-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 18 Twp. 10 Rge. (E) 25 (W)  
Location as "NE/CNW%SW%" or footage from lines SW/4 NW/4 NE/4  
Lease Owner Dane G. Hansen Trust  
Lease Name Hanna 'A' Well No. 3  
Office Address Box 187, Logan, Kansas 67646  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 26 19 68  
Application for plugging filed December 30 19 75  
Application for plugging approved December 31 19 75  
Plugging commenced January 30 19 76  
Plugging completed January 30 19 76  
Reason for abandonment of well or producing formation Oil depleted

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Lansing/K. C. Depth to top 3811 Bottom 4043 Total Depth of Well 4060 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LKC	Oil	3987	3993	8 5/8"	157	None
LKC	Oil	3839	3842	4 1/2"	4059	1615.49'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 3 sacks hulls with water, pumped down.  
Followed with 70 sacks cement mixed with water.  
Mixed 9 sacks gel with water.  
Released plug and pumped 60 sacks cement on top.  
No pressure.

RECEIVED  
3-19-76  
MAR 19 1976  
CONSERVATION DIVISION  
STATE OF KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Company  
Address Box 31, Russell, Kansas


STATE OF KANSAS, COUNTY OF PHILLIPS, ss.  
Dane G. Bales, Manager (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dane G. Bales  
Logan, Kansas 67646  
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of March, 19 76.

Betty Jane Bittel  
Betty Jane Bittel Notary Public.

My commission expires



15-065-20127-0000

WELL LOG

OPERATOR: DANE G HANSEN TR.  
 WELL NAME: HANNA #3 LOCATION: SW NW NE SEC 18-10-25W  
 COUNTY: GRAHAM STATE: KANSAS  
 WELL COMMENCED: MARCH 7, 1968 WELL COMPLETED: MARCH 14, 1968  
 ELEVATION: 2554 KB TOTAL DEPTH: 4060'  
 PRODUCTION: PRODUCING RIG NO: 1  
 CASING - 8-5/8": 8 jts. 157.30 W/140 SACKS QUICKSET  
4 1/2" XXXXX: 126 jts. (4066.98') SET @ 4059'

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
157	205	SHALE	3/4° 550'	
205	1430	SHALE & SAND	1 1/2° 1050'	DST #1 3829-3859'
1430	1760	SHALE	3/4° 1500'	DST #2 3928-4005'
1760	1950	SAND	3/4° 2000'	DST #3 4000-4025'
1950	1980	SHALE & SHELL	3/4° 2500'	
1980	2167	RED BED & SHALE	1 1/4° 3275'	
2167	2204	ANHYDRITE	1° 3819'	
2204	2600	SHALE & SHELLS		
2600	3859	LIME & SHALE		
3859	4060	LIME		

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

DEC 31 1975

C-G DRILLING CO.

By Jay D. Kelly

SUBSCRIBED AND SWORN TO, BEFORE ME, This 18th day of MARCH, 1968.



DEC 7, 1971

Phyllis Buchanan  
PHYLLIS BUCHANAN - NOTARY PUBLIC