


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Nemaha County, Sec. 27 Twp. 2 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Ivan M. Joy
Lease Name Strahm Well No. 1
Office Address 1615 Chase Street, Falls City, Nebr. 68355
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9-13-48 19 48
Application for plugging filed May 5 19 75
Application for plugging approved May 12 19 75
Plugging commenced May 21 19 75
Plugging completed June 12 19 75
Reason for abandonment of well or producing formation not profitable

If a producing well is abandoned, date of last production before purchased
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle D. Hickey
Producing formation Hunton Depth to top 2847 Bottom 2879 Total Depth of Well 2879 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hunton	Oil	2847	2879	5 1/2"	2848'	1100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom of hole 5 sacks of cement, 300 feet from the top of hole set a bridge and put 15 sacks of cement, 50 feet from top of hole set a bridge and put 8 sacks of cement, cut off pipe 24" below ground level and filled pipe to top and on top of pipe with cement.


1975
06-17-75

Name of Plugging Contractor Joy's Machine Shop
Address 1615 Chase Street, Falls City, Nebr. 68355

STATE OF Nebraska, COUNTY OF Richardson, ss.
Ivan M. Joy

well-being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ivan M. Joy
1615 Chase Street Falls City, Nebr.
(Address)



Subscribed and sworn to before me this 15th day of June, 1975
14 April 1979
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg. Wichita, Kansas

COPY

15-131-19017-00-00

Company - CARTER OIL COMPANY
 Farm - Mamie Strahn No. 1

SEC. 27 T. 2 R. 14E
 SW SW NW

Total Depth. 2879
 Comm. 8-10-48 Comp. 9-13-48
 Shot or Treated.
 Contractor. Signal Oil Field Service
 Issued. 12-11-48

County. Nemaha
 KANSAS



Elevation. _____

Production. 54 bbl

CASING:

10 3/4" 169' cement w/115sx circulated
 5 1/2" 2843' cement w/175sx

Figures Indicate Bottom of Formations.

surface soil	234
shale shells	910
lime	980
lime shale	1050
lime	1145
lime shale	1210
shale sand	1317
top of K. C. lime	1337
lime	1580
lime brkn shale	1604
lime shale	1680
sand shale	1720
sand	1730
lime	1760
sand shale	1790
lime shale	1850
lime shale brkn	1863
shale sand	1984
sand shale brks	2049
shale shells	2314
shale sand strks	2443
Mississippi	2451
Mississippi lime	2456
Mississippi cored	2464
Drill stem test	
lime	2600
shale shells	2850
cored RTD	2854
lime hard	2871
shale	2872
lime	2879
Total depth	

Top K. C. Lime 1337

TOPS: SCOUT

Topeka	910
Lansing	1316
Mississippi	2447
Kinderhook	2599
Hunton	2847

RECEIVED
 MAY 19 1975
 05-19-75
 KANSAS GEOLOGICAL SOCIETY