

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY GRAHAM SEC. 23 TWP. 10S RGE. 25 E/W  
Location as in quarters or footage from lines:  
1650 FSL & 990 FEL SW NE SE, SEC. 23-10S-25W


Lease Owner MURJO OIL & ROYALTY COMPANY  
Lease Name KINDERKNECHT Well No. 1  
Office Address P.O. BOX 12666 Ft. Worth, Texas 76116  
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE  
Date Well Completed 12-19-82  
Application for plugging filed 12-23-82  
Plugging commenced 12-18-82  
Plugging completed 12-18-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? PERMISSION WAS OBTAINED

Name of Conservation Agent who supervised plugging of this well GIB SCHECK

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0'	266'	24	J-55 6 Jnts	

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged with 190 sacks 50/50 Poz mix 6% gel, 3% CC. Cement plugs were  
staged at: 20 sacks at 2160', 100 sacks at 1000', 40 sacks at 300',  
10 sacks at 40', 10 sacks rat hole, 10 sacks mouse hole. Final plug  
was down at 9:15 PM.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing - Hays, Kansas



STATE OF Kansas COUNTY OF Sedgwick, ss.  
Arnie Little - Vice President (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Arnie Little 67207  
P.O. Box 18611, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December

Kathleen G. Quinn  
Kathleen G. Quinn  
Notary Public.

My Commission expires: March 20, 1983



15-065-21732-0000

WELL LOG



WELL NAME: KINDERKNECHT #1

WELL LOCATION: SW NE SE, SEC. 23-10S-25W  
GRAHAM COUNTY, KANSAS

OPERATOR: MURJO OIL & ROYALTY COMPANY

COMMENCED: 12-08-82

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 12-19-82

CASING RECORD:  
8 5/8" SET AT 266'  
\_\_\_\_\_  
\_\_\_\_\_

FORMATION:

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>
SAND & SHALE	0'	80'
SAND SOIL	80'	290'
SAND & REDBED	290'	318'
RED/BED	318'	1318'
RED/BED & BLUE SHALE STKS.	1318'	2000'
SHALE	2000'	2229'
LIME & SHALE	2229'	4060'

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED

SW NE SE, SEC. 23-10S-25W, GRAHAM COUNTY, KANSAS TO THE BEST OF MY  
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

*Arnie Little*  
\_\_\_\_\_  
ARNIE LITTLE, VICE - PRESIDENT

DAY OF DECEMBER, 1982

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23RD

MY APPOINTMENT EXPIRES:

KATHLEEN G. QUINN  
STATE NOTARY PUBLIC  
My Appl. Exp. 3-20-83

*Kathleen G. Quinn*  
\_\_\_\_\_  
KATHLEEN G. QUINN NOTARY PUBLIC