

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,363 -0000

LEASE NAME Kinderknecht

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 10 RGE. 25 Cor(W)

COUNTY Graham

Date Well Completed 4-22-87

Plugging Commenced 4-22-87

Plugging Completed 4-22-87

LEASE OPERATOR L.G. Stephenson & Co., Inc.

ADDRESS 1524 North 143rd Street E Wichita, KS 67230

PHONE#(316 733-2465 OPERATORS LICENSE NO. 5462

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dave Wann

to be filed by _____

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 2160' w/25 sacks cement thru drill pipe

Next Plug: @ 1220' w/100 " " " " " & 15 sacks seal flake

Next Plug: @ 250' w/40 " " " " " "

Top Plug: @ 40' w/10 sacks cement & bridged plug 15 sacks in Rat Hole

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or ~~XXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors


(Address) Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28 day of April, 19 87

Dorothy M. Hague
Notary Public

My Commission Expires: 5-5-90

STATE CORPORATION COMMISSION



APR 30 1987

Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas

15-065-22363-0000

DRILLER'S WELL LOG

DATE COMMENCED: April 16, 1987
DATE COMPLETED: April 22, 1987

L.G. Stephenson & Co., Inc.
KINDERKNECHT #1
E/2 NE SE
Sec. 23, T10S, R25W
Graham County, Ks.

ELEVATION: 2476 K.B.

0 - 2142' Surface Soil, Clay, Shale, Sand
2142 - 2182' Anhydrite
2182 - 3530' Lime & Shale
3530 - 3745' Lime
3745 - 3786' Shale & Lime
3786 - 4018' Lime
4018 - 4020' Shale & Lime
4020' RTD

FORMATION DATA

Anhydrite 2142'
Topeka 3530'
Heebner 3745'
Lansing K.C. 3786'
Base K.C. 4018'
RTD 4020'

Surface Pipe; Set
used 8-5/8", 20# @215'
w/145 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 27 day of April 1987.



Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1987

CONSERVATION DIVISION
Wichita, Kansas