

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-005-30367-0000

API NUMBER 15-N/A

LEASE NAME Elrick

WELL NUMBER 8-4

1530 Ft. from S Section Line

890 Ft. from E Section Line

SEC. 9 TWP. 10S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 2-13-59

Plugging Commenced 8-26-93

Plugging Completed 8-26-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Citation Oil & Gas Corp.

ADDRESS 8223 Willow Place S. Ste 250 Houston, TX 77070

PHONE# (713) 469-9664 OPERATORS LICENSE NO. 03553

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-22-93 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Filed with intent to plug

Producing Formation Topeka/ LKC Depth to Top 3762 Bottom 4003 T.D. 4225

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Oil	3762	3768	8 5/8"	248	0
LKC	"	3807	4003	5 1/2"	4212	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. On 8-26-93 Citation MIRU, POOH & LD tbg. RU WL & perf'd 3 shots @ 2150 & 3 shots @ 1240'. Spotted 90 sx 60/40 Poz + 1/4 # Flow Seal +400 # hulls. POOH to 2158' & spotted 100 sx cmt+additive+200# hulls. POOH to 1251' & circ cmt to surface w/100 sx cmt+1/4 #FS. Pmp'd 150 sx cmt down 8 5/8" csg. Pmp'd 50 sx cmt down 5 1/2" to 700 psi. RD PU Cut & cap well. Cleaned location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1108 East 7th Street Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.

Sharon Ward (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Sharon Ward

(Address) 8223 Willow Place S. Ste 250 Houston, TX

SUBSCRIBED AND SWORN TO before me this 30 day of August

Renee Farrell
Notary Public

Notary Public



Expires: 3-2-95

RECEIVED
STATE CORPORATION COMMISSION
SEP 06 1993
CONSERVATION DIVISION
Wichita, Kansas
Revised 05-88