

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 3 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Amanda Hobbs Well No. 2

Location: NE-SE-SE Sec. 18 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 3970' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

176'--8 5/8" Surface pipe, cement circulated with 135 Sx.
Top of Dakota section @ 945'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.
cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
 Conservation Division Agent