

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

12-26-1967  
DEC 26 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Incorporated. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 6504th National Bank Bldg., Wichita, Kansas.

Lease Name: Hobbs Well No. 2

Location: 2610' WEL, 1140' SNL-NE 1/4 Sec. 18 Twp. 10 Rge. (E)(W) 24

County Graham Total Depth 4020 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Pfannenstiel was instructed to plug the well as follows:

221'--8 5/8" surface pipe, cement circulated.  
Dakota section from 950' to 1160'.

Circulate hole with heavy mud. Pull DP to 1180' and displace 100 Sx. cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

K. L. Nichols  
Conservation Division Agent