

State of Kansas



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 10 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Dave Rush Well No. A-3

Location: NE-NE-SW Sec. 20 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 3960 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

174'--8 5/8" Surface pipe, cement circulated with 135 Sx.  
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.  
cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

*M. L. Nichols*  
 Conservation Division Agent