



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

2-19-1963
FEB 19 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ray Richardson of Southwest Csg. Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: D. G. Hanson,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Pfeifer Well No. 1

Location: SW-SW-SW Sec. 4 Twp. 10 Rge. (E)(W) 25

County Graham Total Depth 4110 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Richardson was instructed to plug the well as follows:

Sand well back to 4000', set 4 Sx cement w/dump bailer. Pull
5 1/2" casing to 560', circulate heavy gel mud, displace 20 Sx
cement thru 5 1/2". Pull casing to 180', displace 20 Sx cement
thru 5 1/2". Pull casing set bridge @ 35' and 10 Sx Cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent