

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 1-30-1969
 JAN 30 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Pfeifer Well No. B-1

Location: NW-NW-SE Sec. 4 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4090 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

161'--8 5/8" Surface casing, cement circulated with 125 Sx.

4087'--4 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 4054'. Top perforations @ 3812'.

Push plug to 3750' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing

and squeeze well with 5 sacks hulls plus 30 sacks gel and 130 Sx. cement

staged.

Very truly yours,

M. L. Nichols
 Conservation Division Agent