

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
Z-28-1964
FEB 28 1964

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Glenn Hall of Knight Casing Pulling Co. has this date requested permission to plug the following described well:
Kimbark Exploration Co.
Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Kimbar Exploration Company,
Complete Address: 201 University Blvd., Denver, Colorado.
Lease Name: Pfeifer Well No. 1
Location: SE-SW-SW Sec. 4 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 4070 Oil Well X
Gas Well Input Well SWD Well D & A Lost Hole
Mr. Hall was instructed to plug the well as follows:

196'--8 5/8" Surface pipe, cement circulated. 4070'--4 1/2" production casing cemented with 100 Sx. Plugged back to 4030, top perforations @ ~~3970~~ 3970'.
Sand well back to to 3960' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing to 600' and circulate heavy gel mud. Pull 4 1/2" to ~~540~~ 540' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 190' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set 5' rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols