

15-035-19413-00-00

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC - 6 1965
5-47 CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. D. Spraul of Flint Eng. & Const has this date requested permission to plug the following described well:

Mr. Spraul guarantees payment of the plugging fee.

Operator's full Name: Buckeye Supply Co

Complete Address: Box 1020, El Dorado, Ks.

Lease Name: Lifton Well No. 1

Location: SW SE NW Sec. 24 Twp. 31 Rge. 4 (E) (W)

County Cowley Total Depth 2960 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Spraul was instructed to plug the well as follows:

Plug back to bottom of riser & dump 5'
slts. Cement on top. Pull pipe & set
plug @ 225' 15' rock bridge with
25' slts. Cement on top - set bridge
@ 20' rock bridge with 5' slts. Cement
on top for cap.

Very truly yours,

K. E. Hess

SP 90

Bill Anderson