

#127.27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21557-00-00
Spot: N2N2NWNW Sec/Twnshp/Rge: 6-22S-15W
100 feet from N Section Line, 660 feet from W Section Line
Lease Name: FORD Well #: 1
County: PAWNEE Total Vertical Depth: 3916 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3810		WITH 2 SX CMT
SURF	8.625	971		WITH 450 SX CMT
PC		2710		WITH 125 SX CMT
PROD	5.5	3912	0	WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/07/2010 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DIXON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: SET CIBP @ 3800' & 2 SX CMT. PERFORATE 5 1/2" @ 1000'. PUMP CMT DOWN 5 1/2" & CIRCULATE UP 5 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2010 3:04 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3810' & BAILED 2 SX CMT ON TOP OF PLUG. PERFORATED @ 5 1/2" @ 1000'. RAN TBG TO 1007' & PUMPED 275 SX CMT DOWN TBG. CIRCULATED CMT UP 5 1/2" & 5 1/2" X 8 5/8" ANNULUS. PULLED TBG OUT OF HOLE. TOPPED OFF BOTH STRINGS OF CASING WITH 25 SX CMT. CMT STAYING IN PLACE.

Perfs:

Top	Bot	Thru	Comments
3912	3916		

INVOICED
DATE 4/02/10
INV. NO. 2010061020

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2010

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED

MAR 12 2010

Signed Richard W. Lacey

(TECHNICIAN)

KCC DODGE CITY

Form 6123