

# 100.75

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21205-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 10-16S-17W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: URBAN K Well #: 7  
County: RUSH Total Vertical Depth: 3100 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2700		WITH 2 SX CMT
SURF	8.625	243		WITH 160 SX CMT
PROD	4.5	3094	0	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2010 12:30 PM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: CIBP @ 2700' WITH 2 SX CMT. RUN TBG TO 1200' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2010 1:47 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2700' WITH 2 SX CMT. RAN TBG TO 1200' & CIRCULATED CMT WITH 135 SX CMT. LAID DOWN TBG. PUMPED 30 SX CMT DOWN BACKSIDE. PRESSURED UP TO 300# & BLEW OUT CASING. TOPPED OFF 4 1/2" CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2802	2805		
2749	2752		

INVOICED  
DATE 4/02/10  
INV. NO. 2010061022

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 29 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
MAR 22 2010  
KCC DODGE CITY