

4-031839

6-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,714-0000

NE NW NW /4 SEC. 16, 10 S, 25 W
330 feet from NS section line
990 feet from OE section line

Operator license# 5004 Lease Knoll well # 1

Operator: Vincent Oil Corporation County Graham

Address: 100 N. Main Well total depth 4079 feet 132.56
Suite 300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202-1308 Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: L.D. Drilling, Inc. License# 6039

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 20 Month: June Year: 93

Plugging proposal received from: Greg

Company: L.D. Drilling, Inc. Phone:

Were: Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. - 8 5/8" W.P.
Allied Cementing.
Condition hole before plugging.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:30 P.M., Day: 20, Month: June, Year: 93

Actual plugging report: Spot plugs with drill pipe.
1st. plug with 25 sx. @ 2160'.
2nd. plug with 100 sx. @ 1270'.
3rd. plug with 40 sx. @ 300'.
4th. plug with 10 sx. @ 40' W.P.
Circulate 15 sx. in rathole.
Follow-up check found problem with rathole with no cement in it.
They will fill with cement.

Remarks: Anhy. 2154' - 2192'.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2519 GL

I did / did not X observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
AUG - 2 1993
Carl Goodrow
DH (agent)
Form CP-2/3

INVOICED
DATE AUG 03 1993
INV. NO. 38237