

4-031927

5-19

15-065-01144-00-02

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1956

E2 NE SE /4 SEC. 16, 10 S, 25 W
1980 feet from S section line
330 feet from E section line

Operator license# 4767

Lease Mary Webb "P" well # 1

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
Suite #1000
Wichita, Kansas 67202

Well total depth 4014 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 175 feet

130.45

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 19 Month: May Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling, Inc. Phone:

Were: Order 200 sx. 60/40 pozmix - 10% gel - 500# hulls
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 19, Month: May, Year: 94

Actual plugging report: Sand back to 3700' w/4 sx. common cement on sand
with bailer. Shot at 1950' - 1250'. Pipe tight. Mix and pump 60 sx.
displace 850' - 1950'. Shot at 850' - pipe free. Mix and pump cement
blend to circulate. Used total of 240 sx. cement blend with 1000# hulls
mixed in. Lay down casing, cellar - full of cement. 8 5/8" cement set
@ 175' cwc. 4 1/2" set at 4048' w/200 sx. Prod. perms 3768' - 3986'.
Plug complete.

RECEIVED
STATE CORPORATION
JUN 03 1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did X did not observe the plugging. Carl Goodrow

INVOICED

DATE 6-7-94

INV. NO. 40549

(agent)
Form CP-2/3

HO